

InfraStruxure PDU 60kW 600V/208V

PD60L6FK1

- Discontinued on: Nov 28, 2023
- ! End-of-service on: Feb 21, 2024

① Discontinued

Overview

Presentation	Designed to increase flexibility and agility of data center power distribution through a design that does not require a raised floor.
Lead time	Usually Ships within 3 Weeks

Main

Main Input Voltage	600 V 3 phases	
Main Output Voltage	120 V 208 V 3 phases	
Number of cables	1	
Provided equipment	Installation guide	

Physical

Colour	Black
Height	205.7 cm
Width	61 cm
Depth	91.4 cm
net weight	460 kg
mounting location	Front
Mounting preference	No preference
mounting mode	Not rack-mountable

Input

Network frequency	60 Hz +/- 3 Hz
Max line current	58 A

Output

May current draw	167 A		

Conformance

Standards	LIL 60950	

Environmental

Ambient air temperature for operation	040 °C
Relative humidity	095 %
Operating altitude	03333 ft
Ambient air temperature for storage	-1545 °C
Storage Relative Humidity	095 %
Storage altitude	0.00000000009144.000000000 m

Packing Units

Unit Type of Package 1	PCE
Number of Units in Package 1	1
Package 1 Height	218.4 cm
Package 1 Width	121.9 cm
Package 1 Length	91.4 cm
Package 1 Weight	470 kg

Contractual warranty

Warranty 1 year repair or replace

Sustainability

Green PremiumTM label is Schneider Electric's commitment to delivering products with best-inclass environmental performance. Green Premium promises compliance with the latest regulations, transparency on environmental impacts, as well as circular and low-CO₂ products.

Guide to assessing product sustainability is a white paper that clarifies global eco-label standards and how to interpret environmental declarations.

Learn more about Green Premium >

Guide to assess a product's sustainability >

Eu Rohs Directive

Under investigation